



**NATIONAL INSTITUTE OF PHARMACEUTICAL EDUCATION AND
RESEARCH (NIPER)**

**Sector 67, S.A.S. Nagar (Mohali)
Telephone No. 2214682-87, Fax No. 0172-2214692**

No. NIQ45/2020/17799/

Dated: 25.06.2020

NOTICE INVITING QUOTATION

We are interested in the purchase of the articles mentioned below, please send your quotation addressed to Director, NIPER, clearly specify in outer cover **“quotation for Supply, installation, Testing and Commissioning (S/I/T/C) of Smoke Detectors and Fire Alarm System in National Toxicology Centre (NTC) at NIPER, S.A.S. Nagar and date of opening of quotation”**. The quotation must be accompanied by a forwarding on letter pad of your company mentioning (I) Name of the material, (II) reference of this letter and (III) date of opening of Quotation. Your quotation should be deposited in Tender Box located at Ist Floor Administrative Bhawan, of NIPER on or before **17.07.2020** upto 3.00 p.m. to be opened on **17.07.2020** at 3:30 p.m. in the Conference Room on the first floor of Administrative Bhawan of NIPER in the presence of tenderers, whosoever may wish to be present.

Sr.No.	Description of Materials	Qty
1	Supply, installation, Testing and Commissioning (S/I/T/C) of Smoke Detectors and Fire Alarm System in National Toxicology Centre (NTC) at NIPER, S.A.S. Nagar	As per BOQ

Yours faithfully

AAR (S &P)

Supply, installation, Testing and Commissioning (S/I/T/C) of Smoke Detectors and Fire Alarm System in National Toxicology Centre (NTC) at NIPER, S.A.S. Nagar					
S. No	Description	Qty	Unit	Rate	Amount
1	S/I/T/C of Photo electric/ ionisation smoke detectors,Make Agni / apollo/system sensor	24	No		
2	S/I/T/C manual call point complete with auxiliary contact lamp and front glass ,Make Agni / apollo/system sensor	2	No		
3	S/I/T/C of electronic hooter with built in speaker 100 dB mounted in MS sheet box with cover plate,Make Agni / apollo/system sensor	2	No		
4	S/I/T/C of insulated copper armoured cable 2 x 1.5sqmm ISI marked including PVC pipe/ batten with all fittings etc. As per site requirement Make Finolex/ Havells/ Ecko	390	Metre		
5	S/I/T/C Control Panel solid state circuitry 4 Zone, Microprocessor based, Make Agni / apollo/system sensor	1	No		
		Total			
		GST 18%			
		G. Total (In Figure)			
	G. Total (In words)				

Note : Terms and Conditions

1. 7 Nos. Smoke Detectors to be installed with the existing Four Zone Control Panel and the balance 17 Nos. are to be included in the new Four Zone Control Panel
2. The agency may visit the site to analyse the installations required
3. The rate should include all the costs involved with respect to material, labour, site clearance, accessory required to complete the installation and Testing at site
4. The work should be completed by agency within the one month from the date of order
5. Payment shall be released after complete installation testing etc. To the satisfaction of Engineering Incharge
6. Payment shall be 60 % against delivery of complete material at site
balance 30 % shall be released after successful installation
balance 10 % shall be released after the completion of commissioning and testing
7. The decision of the Director, NIPER, S.A.S.Nagar shall be final and binding on agency with respect to all matters i.e Legal, Administrative, Financial aspects of the said works

I agree to all terms and conditions of the works

Signature of agency with Stamp

List of Proposed Smoke Detectors in NTC, NIPER, S.A.S. Nagar

Frontal Area		
	Locations for smoke detectors	Qty
1	Reception Area	1
2	Conference room	1
3	Veterinarian Room (112)	1
4	QA Room (103)	1
4	Lab Corridor	1
5	Invitro Assay room (105)	1
6	Sample Receiving room (104)	1
Total		7
Back Side (Clean corridor), Clean Room Area & Dirty corridor area		
1	Clean corridor	2
2	Sample Preparation Room (116)	1
3	Quarantine Room (117)	1
4	Quarantine Room (118)	1
5	Sterilized Item Room (119)	1
6	Animal Room (120)	1
7	Animal Room (121)	1
8	Animal Room (122)	1
9	Animal Room (123)	1
10	Autoclav washing Area	1
11	Store Room I(125)	1
12	Store Room II(126)	1
13	Store Room III (127)	1
14	Necropsy lab (111)	1
15	Back Corridor	2
Total		17
Grand Total		24

